



The refurbishment of the BRANZ site includes construction of the new Nikau building – a single-storey, monopitched office space constructed using a post-tensioned LVL portal frame that spans the width of the structure.

Construction process

The construction of the new Nikau building can be separated into five stages:

1. Cast the reinforced concrete foundations.
2. Erect the structure, including the LVL portals, plywood shear walls, roof purlins and roof bracing.
3. Post-tension the LVL portal frames.
4. Close in the building.
5. Internal fit-out.

Fletcher Construction has reached stage 4 and found the construction relatively simple, given that this is the first portal frame to be constructed using this type of structural system. The construction used very tight tolerances that were necessary to ensure the post-tensioned bars fit within the voids of the LVL members, which must align precisely. Fletchers also coordinated the construction between the different sub-contractors, including the LVL fabricators McIntosh Laminates and the post-tensioning contractor BBR Contech.

Lessons from being first

While the Nikau building has been a design, construction and client satisfaction success, a number of lessons have emerged from the new technology on this project:

- Fabrication tolerances mean the LVL beams and columns do not always fit neatly together. (This was complicated by the shear key detail at the end of the beams, which could be simplified on future jobs.)
- Provide sufficient clearance for the post-tensioning jack.
- The LVL fabrication requires tight tolerances to ensure the bearing surface in the beam-column joint is fully activated.
- Architectural details must allow for checking stresses and restressing the bars in the future. ■




Figure 3: The Expan portal column showing the post-tensioned bars.